

State Level Environment Impact Assessment Authority, Rajasthan

Main Building, Room No. 5221, Secretariat, Jaipur.

E-mail : seiaaseiaa2018@gmail.com Phone no. 0141-2227838

No. F1 F1 (4)/SEIAA/SEAC-Raj/Sectt/Project / Cat. 1(a) B1 (15554)/ 2018-19

Dated: 14.5.19

M/s. Ashiana Housing Limited

Add:- 304, Southern Park,

Saket District - Centre,

New Delhi.

Sub:- Environment Clearance of Residentail Project " Ashiana Daksh" at Village Shri Kishanpura, Tehsil- Sanganer, District- jaipur , Rajasthan.(SEIAA no 261,proposal no 29185)

This has reference to your application dated 11.10.18 seeking environmental clearances for the above project under EIA Notification 2006. The proposal has been appraised as per prescribed procedure in the light of provisions under the EIA Notification 2006 on the basis of the mandatory documents enclosed with the application viz. the questionnaire, EIA, EMP and additional clarifications furnished in response to the observation of the State Level Expert Appraisal Committee Rajasthan, in its meeting held on 09-10.04.2019.

Brief details of the Project:

1.	Category / Item no. (in Schedule):	Cat.8(a)B2		
2.	Location of Project	Khasra No'419 to 437(Total khasra 19), Village Shri Kishanpura, Patwar: Vidhani, Tehsil: Sanganer, District - Jaipur, Rajasthan.		
3.	Project Details	S.N.	Particulars	Details
		1.	Total plot area	27013.76 m ² (6.67 acre)
		2.	Gross Built up Area	
		3.	Built up area	61689.66 m ²
		4.	Permissible B.A.R	60780.96m ²
		5.	Utilized B.A.R	54828.12m ²
		6.	Permissible Ground Coverage	9454.81m ²
		7.	Utilized Ground Coverage	9236.8m ²
		8.	Permissible height	-

Shikha

9.	Achieved height	38.85 meter
10.	Proposed Green Area	7191.43 m ²
11.	Total No. of Flat (1 BHK, 2 BHK etc.)	Total 616 Units, (77 EWS Units)
12.	Other facilities like swimming pool, club etc.	Swimming Pool & Club House

Table 25: Existing and proposed land use of Proposed Project

S.No.	Description	Area
		M ²
A.Existing Land – Use		
A-1	Total Plot Area (as Per land document)	27013.76
A-2	Net Plot area	27013.76
A-3	Total Built- up- Area	61689.66

Sl. No.	Description	Unit-Wise area
		M ²
B. Proposed Land- Use		
B-1	BAR Permissible as Per By – laws	60780.96
B-2	BAR Achieved	54828.12
B-3	Ground Coverage Permissible (35%)	9454.81
B-4	Ground Coverage Achieved	9236.8
B-5	Green Area	7191.43
B-7	Open Parking Area	4426
B-8	Road/Paved Area	6160.03
B-9	Total No. of Dwelling Units	616
B-10	Total No. of EWS/ LIG Units	77
B-11	Total No. of Blocks	7
B-12	No. of Floors	S+12 & G+12
B-13	Height of Building	38.85 meter
B-14	Parking Required	558 ECU
B-15	Total Parking Provided	761 ECU

Source : (i) Satellite Imagery Interpretation (ii) Ashiana Housing Limited

4.	Parking	Total Parking required = 558 ECU
----	---------	----------------------------------

Sh. V. V.

		Provision for Parking of -761- E.C.U. has been made as follows:																																																											
		Parking In	Cars	Scooters	Cycle	E.C.U.																																																							
		Open Ground	331	34	-	342																																																							
		Stilt Floor	142	230	36	225																																																							
		Podium parking	157	-	-	157																																																							
		EWS/LIG Parking	-	110	-	37																																																							
		Total E.C.U.	630	374	36	761																																																							
5.	Project Cost:	119.81 Crore																																																											
6.	Water Requirement per day & Source	During construction phase: -It has been estimated that a total of 10 KLD of water will be required for construction labors (@50 lpcd for 200 labors) and source of water supply will be private water tanker. And post construction: -The total water during operation phase is 571 KLD which includes 337 KLD of fresh water and 234 KLD treated water. The water for the project will be sourced from Public health engineering department. Construction Phase: 8.75 KLD of wastewater will be generated during construction phase from the domestic activities which will be treated in soak pits followed by septic tanks.Operation Phase: The total wastewater generation from flushing and domestic activities during operation phase is 412 KLD. Total capacity of STP has been estimated to be 450 KLD. Quantity of recycled water: -The total recycled water from the STP will be approximately 380 KLD. 234 KLD of recycled water will be used for flushing, landscaping and miscellaneous purpose. And remaining 149 KLD would be discharged in nearby agriculture field for irrigation purposes.																																																											
7.	Fuel &Energy:-	Construction Phase: The total power required during construction phase is 50KVA. Operation phase: During Operation phase the estimated electrical load is 3597 kVA. The supply will be provided by JNNVL. Power back-up will be provided by the 2 nos. of DG sets of capacity 380 kVA																																																											
8.	Environment Management Plan with budgetary provision.	Revised Environmental Management Plan (EMP) Cost <table><tr><th colspan="5">ENVIRONMENT MANAGEMENT PLAN (EMP)COST</th></tr><tr><th>S.No.</th><th>Particulars</th><th>Capital Cost</th><th>Breakup</th><th>Amount</th></tr><tr><td>1.</td><td>STP</td><td>10,350,000</td><td>Civil Cost</td><td>7,875,000</td></tr><tr><td></td><td></td><td></td><td>Mechanical cost</td><td>2,475,000</td></tr><tr><td>2.</td><td>Solid waste management</td><td>1,300,000</td><td>Civil Cost</td><td>500,000</td></tr><tr><td></td><td></td><td></td><td>Mechanical cost</td><td>800,000</td></tr><tr><td>3.</td><td>Green Belt</td><td>4,856,302</td><td>Cost per Sft is 7.5</td><td>4,856,302</td></tr><tr><td>4.</td><td>Stack attached to DG set</td><td>750,000</td><td>Material</td><td>450,000</td></tr><tr><td></td><td></td><td></td><td>Labor</td><td>150,000</td></tr><tr><td></td><td></td><td></td><td>Insulation</td><td>150,000</td></tr><tr><td>5.</td><td>Rain Water Harvesting</td><td>1,368,500</td><td>Civil Cost for one RWH is</td><td>1,368,500</td></tr></table>					ENVIRONMENT MANAGEMENT PLAN (EMP)COST					S.No.	Particulars	Capital Cost	Breakup	Amount	1.	STP	10,350,000	Civil Cost	7,875,000				Mechanical cost	2,475,000	2.	Solid waste management	1,300,000	Civil Cost	500,000				Mechanical cost	800,000	3.	Green Belt	4,856,302	Cost per Sft is 7.5	4,856,302	4.	Stack attached to DG set	750,000	Material	450,000				Labor	150,000				Insulation	150,000	5.	Rain Water Harvesting	1,368,500	Civil Cost for one RWH is	1,368,500
ENVIRONMENT MANAGEMENT PLAN (EMP)COST																																																													
S.No.	Particulars	Capital Cost	Breakup	Amount																																																									
1.	STP	10,350,000	Civil Cost	7,875,000																																																									
			Mechanical cost	2,475,000																																																									
2.	Solid waste management	1,300,000	Civil Cost	500,000																																																									
			Mechanical cost	800,000																																																									
3.	Green Belt	4,856,302	Cost per Sft is 7.5	4,856,302																																																									
4.	Stack attached to DG set	750,000	Material	450,000																																																									
			Labor	150,000																																																									
			Insulation	150,000																																																									
5.	Rain Water Harvesting	1,368,500	Civil Cost for one RWH is	1,368,500																																																									

Shubh

			195500	
6.	Pollution monitoring	-		-
7.	Total	18,624,802		18,624,802

S.No.	Description	Annual recurring cost	Breakup	Amount
1.	STP	650,000	Power Consumption	262,000
			AMC	100,000
			Operator	288,000
2.	Solid waste management	155,200	Power Consumption	43,200
			AMC	16,000
			Operator	96,000
3.	Rain Water Harvesting	10,000	Labor charges for maintenance for pits	10,000
4.	Green Belt	120,000	Labor cost for maintenance	120,000
5.	Stack attached to DG set	-		-
6.	Pollution monitoring	75,000	Testing Charges	75,000
7.	Total	1,010,200		1,010,200

19.	CSR Activities	The company intends to spend and amount of Rs. 1.0 Crore approximately in building up infrastructure of a Govt. School along with other developmental works ,children education and skill training The fund outflow will be as under : <table><tr><th>S.No</th><th>Particulars</th><th>FY19-20</th><th>FY 20-21</th><th>FY 21-22</th><th>3 Year Total Amount</th></tr><tr><td>1.</td><td>Infrastructure Development of Government Upper Primary School village -Shree Kishanpura, Sanganer,Jaipur (Rajasthan)</td><td>685,000</td><td>755,000</td><td>516,000</td><td>1,956,000</td></tr><tr><td>2.</td><td>Road Development at Opposite Berwa Hostel Shree Krishan pura</td><td>5,187,000</td><td>-</td><td>-</td><td>5,187,000</td></tr></table>					S.No	Particulars	FY19-20	FY 20-21	FY 21-22	3 Year Total Amount	1.	Infrastructure Development of Government Upper Primary School village -Shree Kishanpura, Sanganer,Jaipur (Rajasthan)	685,000	755,000	516,000	1,956,000	2.	Road Development at Opposite Berwa Hostel Shree Krishan pura	5,187,000	-	-	5,187,000
S.No	Particulars	FY19-20	FY 20-21	FY 21-22	3 Year Total Amount																			
1.	Infrastructure Development of Government Upper Primary School village -Shree Kishanpura, Sanganer,Jaipur (Rajasthan)	685,000	755,000	516,000	1,956,000																			
2.	Road Development at Opposite Berwa Hostel Shree Krishan pura	5,187,000	-	-	5,187,000																			

Shiva

		upto St.Edmund School.																									
		3.	Developing Drainage System with proper Rainwater Harvesting System at opposite Berwa Hostel Shree Krishan pura upto St.Edmund School	1,014,000	549,000	-	1,563,000																				
		4.	Plantation and Green Belt Development at Jeeven Rekha Marg	420,675	326,500	120,000	867,175																				
		5.	Distribution of School Uniform and Tree Plantation	500,000	500,000	-	1,000,000																				
			Total	7,806,675	2,130,500	636,000	10,573,175																				
10	STP	The sewage Treatment Plant (STP) of 450 KLD based on FAB Technology is proposed is to be constructed within the proposed project. The treated wastewater will be used for flushing, landscaping and miscellaneous purposes. There will not be any incremental pollution load on nearby surface water bodies due to proposed project.																									
11	Green Belt/ Plantation area and % of total area in sq. mts.	An area of 7191.43 m ² has been identified for greenbelt development. Total area for greenbelt development is 26.62 % of Net Plot area. The green area should be properly maintained and dead plants should be regularly replaced.																									
12	Budgetary Breakup for Labour	<u>DETAILS OF FACILITY TO BE PROVIDED TO CONSTRUCTION LABOURERS ALONG WITH BUDGETARY PROVISION</u> <table><tr><th>S.NO</th><th>PARTICULARS</th><th>PROVISIONS</th><th>BUDGET</th></tr><tr><td>1.</td><td>Shelter, basic facilities</td><td>A provision of temporary Housing facility along basic facility for construction workers will be provided</td><td>3.0</td></tr><tr><td>2.</td><td>Drinking water</td><td>Clean drinking water will be made available at suitable points</td><td>1.0</td></tr><tr><td>3.</td><td>Sanitation facility</td><td>There will be up to 200 (peak - construction) workers hence proper toilets facility with soak pit will be duly provided as per norms.</td><td>3.0</td></tr><tr><td>4.</td><td>Health Facility & Arrangements</td><td>A first aid room with equipped First-aid boxes and cupboards will be accessible during the hours of working in the construction and operation phase.</td><td>2.0</td></tr></table>						S.NO	PARTICULARS	PROVISIONS	BUDGET	1.	Shelter, basic facilities	A provision of temporary Housing facility along basic facility for construction workers will be provided	3.0	2.	Drinking water	Clean drinking water will be made available at suitable points	1.0	3.	Sanitation facility	There will be up to 200 (peak - construction) workers hence proper toilets facility with soak pit will be duly provided as per norms.	3.0	4.	Health Facility & Arrangements	A first aid room with equipped First-aid boxes and cupboards will be accessible during the hours of working in the construction and operation phase.	2.0
S.NO	PARTICULARS	PROVISIONS	BUDGET																								
1.	Shelter, basic facilities	A provision of temporary Housing facility along basic facility for construction workers will be provided	3.0																								
2.	Drinking water	Clean drinking water will be made available at suitable points	1.0																								
3.	Sanitation facility	There will be up to 200 (peak - construction) workers hence proper toilets facility with soak pit will be duly provided as per norms.	3.0																								
4.	Health Facility & Arrangements	A first aid room with equipped First-aid boxes and cupboards will be accessible during the hours of working in the construction and operation phase.	2.0																								

SMW

		5.	Fuel for Cooking	LPG gas connection by individually	3.0
		6.	Safeguards	All protective and safety gears will be provided. Helmets, face masks, Safety gloves as per requirement, safety belt, gum boots and goggles will be provided to the workers.	1.0
		7.	Medical Examination	An examination of every person employed in the construction activity will be done. The periodic medical examination will be done at regular intervals.	1.0
		8.	Education for their children -Creche recreation	Creche and phoolwari School will be provided at site. Teacher will be provided for teaching children of construction workers.	1.0
		Total			15 Lacs

The SEAC Rajasthan after due considerations of the relevant documents submitted by the project proponent and additional clarifications/documents furnished to it have recommended for Environmental Clearance with certain stipulations. The SEIAA Rajasthan after considering the proposal and recommendations of the SEAC, Rajasthan in its 4.12th Meeting held on 14.05.2019 hereby accord Environmental Clearance to the project as per the provisions of Environmental Impact Assessment Notification 2006 and its subsequent amendments, subject to strict compliance of the terms and conditions as follows:

PART A: SPECIFIC CONDITIONS—

CONSTRUCTION PHASE

1. Consent to Establish" shall be obtained from RPCB before start of any construction work related to proposed project at the site.
2. The PP shall obtain a "No objection certificate" for height clearance for the envisaged level from the Airports Authority of India.
3. No Mobile tower shall be installed.
4. Solar panels for common services areas shall be provided.
5. Provision for compost pit for dry leaves shall be provided.
6. Provision for drinking water supply for the residents from a legal source shall be made.
7. As envisaged, the P.P. shall invest the an amount of **Rs. 18,624,802 as capital cost and Rs. 1,010,200 as annual recurring cost** for implementing various environmental protection measure.
8. An amount of **Rs. 1.8 Crores** is required to be spent over a period of 3 years on CER activities (as decided by the committee). The expenditure on these activities shall be reflected in the books of account when presented for auditing of accounts. The proposal should contain provision for toilets for girls in nearby schools. The proposal should contain provision for monthly medical

Shweta

camps, distribution of medicines and improvement in educational facilities in the nearby schools. The detailed action plan of CSR activities shall be submitted by the PP to RSPCB at the time of applying for Consent to Establish/Consent to Operate. During construction phase and post construction / operation phase, the project proponent shall be responsible for implementation of EIA/EMP. Commitment of proponent in this regard shall be submitted to RPCB at the time of applying for CTE/CTO.

9. Green belt/Landscaping should be developed in **7191.43 m²**. (26.62 %) of total plot Area, as proposed.
10. This E.C. is issued from the environmental angle only, and does not absolve the project proponent from the other statutory obligations prescribed under any other law or any other instrument in force. The sole and complete responsibility to comply with the conditions laid down in all other laws for the time-being in force, rests with the industry / unit / project proponent. Any appeal against this environmental clearance lies with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under section 16 of the National Green Tribunal Act, 2010.
11. For conservation of electricity and to reduce energy losses the management shall ensure that the electrical voltage is stepped down from 33 KV to 11 KV and distributed at this level and finally brought to 440 volts or as per prescribed norms.
12. The PP shall obtain approval of drawings of laying electrical lines from the concerned SE of RRVPNL/ JVVNL and comply with the provisions as per Terms and Conditions for Supply of Electricity-2004 of JVVNL.
13. The PP shall fulfill the requirements of energy regulatory commission.
14. All energy saving measures proposed by the PP should be implemented before the project is put into use.
15. A preventive action plan (as part of conceptual plan) for earthquake resistance buildings as per NBC code specifically for zone 3,4, 5 should be submitted along with the **Form 1 , Form 1A** and conceptual plan to RSPCB at the time of applying for CTE /CTO.
16. Road width and bend should be adequate for easy movement of fire fighting vehicles.
17. Proposals for provisions regarding accessibility to the various floors of the project and other related parts for Divyang people should be provided.
18. Details of all the points mentioned at point no. 9 under energy conservation of Form IA would be explicitly taken care of.
19. The P.P. shall ensure taking necessary steps on urgent basis to improve the living conditions of the labour at site. An amount of **Rs.15.0 Lac** shall be spent as Budgetary provision for the housing of construction labour within the site with all necessary infrastructure and facilities such as health, sanitation, fuel/LPG for cooking, safe drinking water, medical camps, toilets for women and crèche for infants etc. Such housing may be in the form of temporary structures to be removed after the completion of the project. Details of provisions should be submitted to RPCB at the time of obtaining CTE.
20. The PP will comply with the provisions as per the Building and Other Construction Workers (Regulation of Employment & Condition of Service) Act 1996.
21. The STP should be so designed so that it can cater the minimal flow due to lesser occupancy in the project so as to bring the waste water quality as per the prescribed standards.
22. The drains should be of adequate capacity and be lined till the final disposal points.

Shw

23. The entire waste water should be treated through a STP of **capacity 450 KLD of FAB** technology. The construction of the STP should be carried out simultaneously with that of the project and the STP should be functional before the project is put into use. The STP should have a separate hour meter and energy meter.
24. The PP shall comply with Construction & Demolition Waste Management Rules, 2016 as applicable.
25. All required sanitary and hygienic measures shall be put in place before starting construction activities. The safe disposal of waste water and solid waste generated during the Construction phase shall be ensured.
26. All the laborers engaged for construction shall be screened for health and adequately treated before engaging them to work at the site.
27. All the topsoil excavated during the construction shall be stored for use in horticulture/landscape development within the project site.
28. Disposal of muck during construction phase should only be at approved sites with the approval of competent authority. It should not create any adverse effect on the neighboring communities and be disposed by taking necessary precautions for general safety and health aspects of the people.
29. Soil and ground water samples will be tested to ascertain that there is no threat to the ground water quality by leaching of heavy metals and other toxic contaminants.
30. Construction spoils, including bituminous material and other hazardous materials must not be allowed to contaminate water courses and the dump sites for such material must be secured so that they do not leach into the ground water.
31. The diesel generator sets to be used during and post construction phase shall be of low-sulphur-diesel type and shall conform to Environment (Protection) Rules for air and noise emission standards.
32. Vehicles hired for bringing construction material and laborers to the site shall be in good conditions and shall conform to applicable air and noise emission standards and shall be operated during non-peak/approved hours.
33. Ambient noise levels shall conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality shall be closely monitored during construction phase.
34. Fly ash shall be used as building material in the construction as per the provisions of Fly Ash notification of September, 1999 and as amended till date.
35. NOC shall be obtained from National State Disaster Management Authority wherever applicable.
36. Provision for proposed storm water harvesting and its re-use as per CGWA and BIS standards for various applications should be implemented before the project is put into use.
37. Guidelines issued by concerned Ministry for water scarce areas be followed.
38. Water demand during construction shall be reduced by the use of pre-mixed concrete, curing agents and other best practices. Effort should be made to use treated waste water from nearby areas in place of fresh water.
39. Total domestic water requirement during construction phase shall be 10 KLD and during operational phase shall be 571 KLD (337 KLD Fresh + 234 KLD treated), as proposed. The necessary permission of water supply should be submitted to RSPCB at the time of applying for CTE/CTO. At the time of applying for CTE the PP should get it confirmed from RSPCB that no illegal bore well exists in the proposed site.

Sh. K. K.

40. Building Plan should be got approved from the competent Authority and the construction should be as per the approved building plan and as per applicable provisions in NBC.
41. The P.P. should ensure compliance of the order of the Hon'ble Rajasthan High Court, Jodhpur in D. B. Civil writ petition no. 1536 of 2003 in the matter of Abdul Rahman vs. State of Rajasthan and others. The PP shall not allow making of any obstacle in the way of any natural water course/natural nallaha/stream carrying rain water to any water body. Adequate measures shall be taken to reduce air and noise pollution during construction as per CPCB norms.
42. Fixtures for showers, toilet flushing and drinking shall be of low flow either by use of aerators of pressure reducing devices or sensor based control.
43. Use of glass may be reduced by up to 40% to reduce the electricity consumption and load in air-conditioning. If necessary, use high quality double glass with special reflective coating windows.
44. Roofing should meet prescriptive requirement as per Energy Conservation Building Code by using appropriate thermal insulation material to fulfill requirement.
45. Opaque walls shall meet prescriptive requirement as per Energy Conservation Building Code for all air-conditioned spaces, whereas, for non- air-conditioned spaces, by use of appropriate thermal insulation material to fulfill the requirement.
46. Provision of solar water heating /chilling/street lighting etc shall be explored and implemented.
47. A first-aid room should be provided at the project site, both, during construction and operation phase of the project.
48. Any hazardous waste generated during construction phase shall be disposed of as per applicable rules and norms with necessary authorization of the RPCB.
49. The approval of the competent authority shall be obtained for structural safety of the building due to earthquake, adequacy of firefighting equipment, etc. as per National Building Code 2005 including protection measures from lightening etc.
50. Regular supervision of the above and other measures for monitoring shall be in place throughout the construction phase, so as to avoid nuisance to the surroundings.
51. The project proponent shall fulfill in letter and spirit, all the commitments made /submitted to the SEAC office.
52. The Company shall provide stacks of adequate height to the along with acoustic enclosures for noise control as per CPCB guidelines. The DG Sets (2*380 KVA) shall comply with the norms notified under Environment (Protection) Act, 1986.
53. The PP shall obtain all requisite permissions/ approvals/clearances from concerning departments and district administration relating to project.
54. The PP shall procure required fresh water only from the authorized and legal source after approval from the competent Authority and such procurement of water shall be informed to RSPCB at time of applying for CTO/CTE.
55. The PP shall provide water flow meter at all suitable points to measure quantity of daily water consumption. Besides PP shall also provide water flow meters at waste water generation points, treated waste water, waste water recycled and utilized for plantation / gardening purposes. The daily record of this should be maintained properly in a logbook.
56. The PP shall dispose of the sludge of STP in Scientific manner.
57. The PP shall make compliance of the standards, for Noise and National Ambient Air Quality, as prescribed under the Environment (Protection) Act 1986.
58. The total waste water generation will be utilized and disposed as proposed.

Sharma

59. The PP shall not discharge treated waste water in to any natural water flow or in to any water body but make efforts to utilize maximum of the treated effluent within the premises of the project.
60. The PP shall ensure that solid waste generated should be properly collected & segregated. Wet garbage should be composed and dry/inert solid waste should be disposed off at approved sites for land filling after recovering recyclable material.
61. The CFs/FLs / E-waste should be properly collected and disposed off/ sent for recycle as per the prevailing rules / guidelines issued by the regulatory authority. Use of solar panel also may be done to the possible extent.
62. The adequate measure should be taken to prevent odour problem form STP.
63. The PP should obtain prior Consent to Operate before commissioning of the project or handed over to the occupier.
64. The PP shall provide and maintain the O&G trap in good condition, so that the O&G coming with Waste Water from Kitchen/laundry should retain in trap.

OPERATION PHASE

1. An independent expert shall certify the installation of the Sewage Treatment Plants (STP) and a report in this regard shall be submitted to the RPCB, before the project is commissioned for operation. Discharge of treated sewage shall conform to the norms & standards prescribed under the Environment (Protection) Act 1986 or the standards laid down by the Rajasthan State Pollution Control Board.
2. Adequate measures shall be taken to prevent odour from solid waste processing and STP.
3. Proper system of channelizing excess storm water shall be provided.
4. Rain Water harvesting (RWH) for roof top run-off and surface run-off, as planned shall be implemented. Before recharging the surface run off, pre-treatment must be done to remove suspended matter, oil and grease. The Rain Water Harvesting plan shall be as per Gol manual.
5. The proposals on the energy conservation measures conforming to energy conservation norms finalized by Bureau of Energy Efficiency shall be implemented.
6. The power factor shall be maintained near unity.
7. Application of solar energy shall be incorporated for illumination of common areas, lighting for gardens and street lighting in addition to provision for solar water heating. A hybrid system or fully solar system for a portion of the apartments shall be provided.
8. The parking place shall have separate entry and exit points. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking shall be fully internalized and no public space shall be utilized.
9. Regular and periodic mock drills shall be undertaken by the fire department at least once in a year.
10. The D. G. sets to be operated with stack height as per EP Act, 1986 along with acoustic enclosure.
11. Incremental pollution loads on the ambient air quality noise and water quality shall be periodically monitored after commissioning of the project and report to be submitted to RPCB.
12. The solid waste generated shall be properly collected & segregated before disposal to the City Municipal Facility. The in-vessel bio-conversion technique may be used for composting the organic waste.

Shree

13. Any hazardous waste including biomedical waste shall be disposed of as per applicable Rules & norms with necessary approvals of the Rajasthan State Pollution Control Board.
14. The green belt design along the periphery of the plot shall achieve attenuation factor conforming to the day and night noise standards prescribed for residential land use. The proposed open space inside the plot shall be suitably landscaped and covered with vegetation of indigenous species.
15. Local species of trees and shrubs shall be planted to allow habitat for birds with adequate distance from the boundary.
16. The SEIAA, Rajasthan reserve the right to add new conditions, modify/ annual any condition and/or to revoke the clearance if implementation of any of the aforesaid condition/other stipulations imposed by competent authorities is not satisfactory. Six monthly compliance status report of the project along with implementation of environmental measures shall be submitted to MoEF, Regional Office, Lucknow, SEIAA, Rajasthan & RPCB, Jaipur.
17. The PP shall provide adequate and proper compost pit for utilization of all the leaf litter and ensure that such waste should not be burnt.

General Conditions:

1. This E.C. is issued from the environmental angle only, and does not absolve the project proponent from the other statutory obligations prescribed under any other law or any other instrument in force. The sole and complete responsibility, to comply with the conditions laid down in all other laws for the time-being in force, rests with the industry / unit / project proponent. Any appeal against this environmental clearance shall lie with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under section 16 of the National Green Tribunal Act, 2010.
2. No further expansion or modifications in the project shall be carried out without prior approval of the SEIAA/Ministry of Environment and Forests as the case may be. In case of deviations or alterations in the project proposal from those submitted to this Authority for clearance, a fresh reference shall be made to the Authority to assess the adequacy of conditions imposed and to add additional environmental protection measures required, if any.
3. The implementation of the project vis-à-vis environmental action plans shall be monitored by MoEF Regional Office at Lucknow / RSPCB / CPCB / SEIAA, Department of Environment, Government of Rajasthan, Jaipur and this office. A six monthly compliance status report shall be submitted to monitoring agencies.
4. The EC is liable to be rejected, in case it is found that the PP has deliberately concealed and furnished false and misleading information or data which is material to screening or scoping or appraisal or decision on the application for EC.
5. The project authorities shall inform the MoEF Regional Office at Lucknow / RSPCB / CPCB / SEIAA, Department of Environment, Government of Rajasthan, Jaipur and the date of financial closure and final approval of the project by the concerned authorities and the date of start of the project.
6. Officials from the Department of Environment, Government of Rajasthan, Jaipur/ Regional Office of MoEF, Lucknow, RSPCB who would be monitoring the implementation of Environmental safeguards should be given full cooperation, facilities and documents/data by the project proponents during their inspection. A complete set of all the documents submitted to SEIAA should be forwarded to the CCF, Regional Office of MoEF, Lucknow / SEIAA, Department of Environment, Government of Rajasthan, Jaipur / RSPCB.

Shinba

7. The Authority reserves the right to add additional safeguard measures subsequently, if found necessary, and to take action including revoking of the environment clearance under the provision of the Environment (Protection) Act, 1986, to ensure effective implementation of the suggested safeguard measures in a time bound and satisfactory manner.
8. The project proponent should advertise in at least two local Newspapers widely circulated in the region, one of which shall be in the vernacular language informing that the project has been accorded environmental Clearance and copies of clearance letters are available with the Rajasthan State Pollution Control Board and may also be seen on the website of the RSPCB. The advertisement should be made within 7 days from the day of issue of the clearance letter and a copy of the same should be forwarded to the Regional Office of MoEF at Lucknow/Department of Ecology and Environment, Government of Rajasthan, Jaipur.
9. These stipulations would be enforced among others under the provisions of water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986, the Public Liability (Insurance) Act, 1991 and EIA Notification, 2006, along with their amendments and rules.
10. The PP shall obtain prior clearance from forestry and wild Life angle including clearance from standing committee of National Board of Wild Life (as applicable). It is further categorically stated that grant of EC does not necessary implies that Forestry and Wild Life clearance shall be granted to the project and that proposals for forestry and wild Life clearance will be considered by the respective authorities on their merits and decision taken. The investment made in the project, if any based on EC so granted, in anticipation of clearance from Forestry and Wild Life angle shall be entirely at the cost risk of the PP and MOEF/SEIAA shall not be responsible in this regard in any manner.
11. The SEIAA, Rajasthan may revoke or suspend the clearance, if implementation of any of the above conditions is not found satisfactory.
12. Periodic monitoring of ambient air quality shall be carried out for PM10, PM2.5, SPM, SO2 and NOx monitoring. Location of the stations (minimum 6) shall be decided based on the meteorological data, topographical features and environmentally and ecologically sensitive targets and frequency of monitoring shall be decided in consultation with the Rajasthan State pollution Control Board (RPCB). Six monthly reports of the data so collected shall be regularly submitted to the RPCB/CPCB including the MoEF, Regional office, Lucknow.
13. Personnel working in dusty areas shall wear protective respiratory devices they shall also be provided with adequate training and information on safety and health aspects.
14. The ambient noise level should conform to the standards prescribed under E (P) A Rules, 1986 viz 75 dB (A) during day time and 70 dB (A) during night time.
15. The environmental statement for each financial year ending 31st March in Form-V shall be submitted to the Rajasthan State Pollution Control Board/SEIAA as prescribed under the environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of environmental clearance conditions and shall also be sent to the Lucknow Regional offices of MoEF/SEIAA by e-mail as well as hard copy dually signed by competent person of company.

Shikha

Shikha
(Shikha Mehra)
Member Secretary,
SEIAA, Rajasthan.

No. F1 (4)/SEIAA/SEAC-Raj/Sectt/Project / Cat. 1(a) B1 (15554)/ 2018-19 Dated: 14.5.19

Copy to following for information and necessary action:

1. Secretary, Ministry of Environment, Forest & Climate Change, Govt. of India, Indira Paryavaran Bhawan, JorBagh Road, Aliganj, New Delhi-1 10003.
2. Principal Secretary, Environment Department, Rajasthan, Jaipur.
3. Sh. R.K. Meena, IAS (Retd.), B-75, Shankar Vihar, 50 Feet Gaitore Road, Sawai Gaitor, Jaipur
4. Dr. Anil Kumar Goel IFS (Retd.), Forest Colony, Sector 4, Jawahar Nagar, Jaipur.
5. Member Secretary, Rajasthan State Pollution Control Board, Jaipur for information & necessary action and to display this sanction on the website of the Rajasthan Pollution Control Board, Jaipur.
6. Sh Rajesh Thakuriya, Member Secretary, SEAC Rajasthan.
7. The CCF, Regional Office, Ministry of Environment & Forests, RO(CZ), Kendriya Bhawan, 5th Floor, Sector 'H', Aliganj, Lucknow-226 020.
8. Environment Management Plan- Division, Monitoring Cell, Environment, Forest & Climate Change, Govt. of India, Indira Paryavaran Bhawan, JorBagh Road, Aliganj, New Delhi-110003.
9. Sh. Jagbir Singh Manral, ACP, Department of Environment, Government of Rajasthan, Jaipur with the direction to upload the copy of this Environment Clearance on the website.

M.S. SEIAA
(Rajasthan)

No. F1 (4)/SEIAA/SEAC-Raj/Sectt/Project / Cat. 1(a) B1 (15554)/ 2018-19 Dated: 14.5.19

Copy to following for information and necessary action:

1. Secretary, Ministry of Environment, Forest & Climate Change, Govt. of India, Indira Paryavaran Bhawan, JorBagh Road, Aliganj, New Delhi-110003.
2. Principal Secretary, Environment Department, Rajasthan, Jaipur.
3. Sh. R.K. Meena, IAS (Retd.), B-75, Shankar Vihar, 50 Feet Gaitore Road, Sawai Gaitore, Jaipur.
4. Dr. Anil Kumar Goel IFS (Retd.), Forest Colony, Sector 4, Jawahar Nagar, Jaipur.
5. Member Secretary, Rajasthan State Pollution Control Board, Jaipur for information & necessary action and to display this sanction on the website of the Rajasthan Pollution Control Board, Jaipur.
6. Sh. Rajesh Thakuriya, Member Secretary, SEAC Rajasthan.
7. The CCF, Regional Office, Ministry of Environment & Forests, RO(CZ), Kendriya Bhawan, 5th Floor, Sector 'H', Aliganj, Lucknow-226 020.
8. Environment Management Plan- Division, Monitoring Cell, Environment, Forest & Climate Change, Govt. of India, Indira Paryavaran Bhawan, JorBagh Road, Aliganj, New Delhi-110003.
9. Sh. Jagbir Singh Manral, ACP, Department of Environment, Government of Rajasthan, Jaipur with the direction to upload the copy of this Environment Clearance on the website.

M.S. SEIAA
(Rajasthan)