

State Level Environment Impact Assessment Authority, Rajasthan

4, Institutional Area, Jhalana Doongri, Jaipur-302004

Phone: 0141-2705633, 2711329 Ext. 361

No. F1 (4)/SEIAA/SEAC-Raj/Sectt/Project/Cat. 8(a)B2 (1352)/14-15 Jaipur, Dated: **11 MAR 2016**

To,

M/s Suncity Projects Pvt. Ltd.,

Suncity Business Tower 2nd Floor,

Golf Course Road,

Sector-54, Gurgaon, Haryana.

Sub:-Regarding Environmental Clearance of Residential Colony "Jewel of India"
Khasra No. 180, 181, 184 & 186, Village Jhalana Dungar Tehsil Sanganer, District
Jaipur, Rajasthan by M/s Suncity Projects Pvt. Ltd.

This has reference to your application dated 31.07.2014 seeking environmental clearances for the above project under EIA Notification 2006. The proposal has been appraised as per prescribed procedure in the light of provisions under the EIA Notification 2006 on the basis of the mandatory documents enclosed with the application viz. the questionnaire, EIA, EMP and additional clarifications furnished in response to the observation of the State Level Expert Appraisal Committee Rajasthan, in its meeting held on 28.12.15

Brief details of the Project:

1.	Category / Item no. (in Schedule):	Cat.8(a) B2																																	
2.	Location of Project	Khasra Nos. 180, 181, 184 & 186, Village Jhalana Dungar, Tehsil Sanganer, Jaipur, Rajasthan																																	
3.	Project Details	<table><tr><th colspan="3">AREA STATEMENT (Option 1)</th></tr><tr><th>S.N</th><th>Particulars</th><th>Details (m²)</th></tr><tr><td>1.</td><td>Total plot area</td><td>74147</td></tr><tr><td>2.</td><td>Surrender Area - Area 1 - Area 2 </td><td>2529 1180 1349</td></tr><tr><td>3.</td><td>Net Plot Area</td><td>71618</td></tr><tr><td>4.</td><td>Permissible F.A.R. (@2 of plot area)</td><td>148294.00</td></tr><tr><td>5.</td><td>Utilized F.A.R. (@1.821 of plot area) - Residential - Commercial </td><td>135022.39 106341.12 28681.27</td></tr><tr><td>7.</td><td>Non-FAR Area at Floors</td><td>39945.93</td></tr><tr><td>8.</td><td>Services Area at ground</td><td>1285.0</td></tr><tr><td>9.</td><td>Area under Club</td><td>3382.52</td></tr><tr><td>10.</td><td>Basement Basement 1 Basement 2</td><td>100292.15 50146.08 50146.08</td></tr></table>	AREA STATEMENT (Option 1)			S.N	Particulars	Details (m ²)	1.	Total plot area	74147	2.	Surrender Area - Area 1 - Area 2	2529 1180 1349	3.	Net Plot Area	71618	4.	Permissible F.A.R. (@2 of plot area)	148294.00	5.	Utilized F.A.R. (@1.821 of plot area) - Residential - Commercial	135022.39 106341.12 28681.27	7.	Non-FAR Area at Floors	39945.93	8.	Services Area at ground	1285.0	9.	Area under Club	3382.52	10.	Basement Basement 1 Basement 2	100292.15 50146.08 50146.08
AREA STATEMENT (Option 1)																																			
S.N	Particulars	Details (m ²)																																	
1.	Total plot area	74147																																	
2.	Surrender Area - Area 1 - Area 2	2529 1180 1349																																	
3.	Net Plot Area	71618																																	
4.	Permissible F.A.R. (@2 of plot area)	148294.00																																	
5.	Utilized F.A.R. (@1.821 of plot area) - Residential - Commercial	135022.39 106341.12 28681.27																																	
7.	Non-FAR Area at Floors	39945.93																																	
8.	Services Area at ground	1285.0																																	
9.	Area under Club	3382.52																																	
10.	Basement Basement 1 Basement 2	100292.15 50146.08 50146.08																																	

11.	Gross Built up Area	279927.99				
12.	Built up area	279927.99				
13.	Permissible Ground Coverage (35% of plot area)	25066.30				
14.	Utilized Ground Coverage Coverage (23.89% of net plot area) • Residential • Commercial	17112.2 12591.62 4520.6				
15.	Permissible height	-				
16.	Achieved height	33.95 m				
17.	Landscape Area (35.14% of net plot area)	25167.59				
18.	Open Parking Area	5919.92				
19.	Total No. of Flat (1 BHK, 2 BHK etc.)	Unit Type	Type of unit	Nos	Total Nos.	
		Residential Block				
		4 BHK	B1	144	224	
			B2	80		
		5 BHK	A1	24	124	
			A2	60		
			A3	40		
		Pent House	B2	8	18	
			A2	6		
			A3	4		
Total				366		
Commercial Block						
Service Apartment	Commercial block (3 rd - 10 th F)	341	341			
Staff @ Retail shops	Commercial block (GF-2 nd F)	48	48			
20.	Other facilities like swimming pool, club etc.	Club, Swimming Pool				
AREA STATEMENT (Option 2)						
S.N	Particulars	Details (m ²)				
1.	Total plot area	74147				
2.	Surrender Area	2529				
	• Area 1	1180				
	• Area 2	1349				
3.	Net Plot Area	71618				

4.	Permissible F.A.R. (@2 of plot area)	148294.00																																																		
5.	Utilized F.A.R. (@1.998 of plot area) • Residential • Commercial	148132.24 119450.97 28681.27																																																		
7.	Non-FAR Area at Floors	42754.89																																																		
8.	Services Area at ground	1285.00																																																		
9.	Area under Club	3382.52																																																		
10.	Basement Basement 1 Basement 2	100292.15 50146.08 50146.08																																																		
11.	Gross Built up Area	295845.8																																																		
12.	Built up area	295845.8																																																		
13.	Permissible Ground Coverage (35% of plot area)	25066.30																																																		
14.	Utilized Ground Coverage Coverage (23.89% of net plot area) • Residential • Commercial	17112.2 12591.62 4520.6																																																		
15.	Permissible height	-																																																		
16.	Achieved height	42 m																																																		
17.	Landscape Area (35.14% of net plot area)	25167.59																																																		
18.	Open Parking Area	5919.92																																																		
19.	Total No. of Flat (1 BHK, 2 BHK etc.)	<table><tr><th>Unit Type</th><th>Type of unit</th><th>Nos.</th><th>Total Nos.</th></tr><tr><td colspan="4">Residential Block</td></tr><tr><td rowspan="3">4 BHK</td><td>B1</td><td>156</td><td rowspan="3">248</td></tr><tr><td>B2</td><td>48</td></tr><tr><td>B3</td><td>44</td></tr><tr><td rowspan="3">5 BHK</td><td>A1</td><td>28</td><td rowspan="3">148</td></tr><tr><td>A2</td><td>72</td></tr><tr><td>A3</td><td>48</td></tr><tr><td rowspan="4">Pent House</td><td>B2</td><td>4</td><td rowspan="4">18</td></tr><tr><td>A2</td><td>6</td></tr><tr><td>A3</td><td>4</td></tr><tr><td>B3</td><td>4</td></tr><tr><td colspan="3">Total</td><td>414</td></tr><tr><td colspan="4">Commercial Block</td></tr><tr><td>Service Apartment</td><td>Commercial block (3rd - 10th F)</td><td>341</td><td>341</td></tr><tr><td>Staff @ Retail shops</td><td>Commercial block (GF-2nd F)</td><td>48</td><td>48</td></tr></table>	Unit Type	Type of unit	Nos.	Total Nos.	Residential Block				4 BHK	B1	156	248	B2	48	B3	44	5 BHK	A1	28	148	A2	72	A3	48	Pent House	B2	4	18	A2	6	A3	4	B3	4	Total			414	Commercial Block				Service Apartment	Commercial block (3 rd - 10 th F)	341	341	Staff @ Retail shops	Commercial block (GF-2 nd F)	48	48
Unit Type	Type of unit	Nos.	Total Nos.																																																	
Residential Block																																																				
4 BHK	B1	156	248																																																	
	B2	48																																																		
	B3	44																																																		
5 BHK	A1	28	148																																																	
	A2	72																																																		
	A3	48																																																		
Pent House	B2	4	18																																																	
	A2	6																																																		
	A3	4																																																		
	B3	4																																																		
Total			414																																																	
Commercial Block																																																				
Service Apartment	Commercial block (3 rd - 10 th F)	341	341																																																	
Staff @ Retail shops	Commercial block (GF-2 nd F)	48	48																																																	
20.	Other facilities like	Club, Swimming Pool																																																		

		swimming pool, club etc.																																																														
4.	Parking	Total Parking required = 2708 <table><thead><tr><th>Category</th><th>FAR (sq m)</th><th>Parking Required</th><th>No. of ECS Required</th></tr></thead><tbody><tr><td colspan="4">Residential Block</td></tr><tr><td>Residents</td><td>119450.97</td><td>1 ECS/75 sq m of FAR</td><td>1593</td></tr><tr><td>Visitors</td><td>---</td><td>25% of parking required</td><td>398</td></tr><tr><td colspan="3">Total Parking Residential Block</td><td>1991</td></tr><tr><td colspan="4">Commercial Block</td></tr><tr><td>Residents</td><td>28681.27</td><td>1 ECS/50 sq m of FAR</td><td>574</td></tr><tr><td>Visitors</td><td></td><td>25% of parking required</td><td>143</td></tr><tr><td colspan="3">Total Parking Commercial Block</td><td>717</td></tr><tr><td colspan="3">Total Parking</td><td>2708</td></tr></tbody></table> Provision for Parking of 2712 E.C.S. has been made as follows: <table><thead><tr><th>Parking</th><th>Total Car Parking Provided</th><th>Total Scooter Parking provided</th></tr></thead><tbody><tr><td>Surface</td><td>212</td><td>0</td></tr><tr><td>First Basement</td><td>924</td><td>1024</td></tr><tr><td>Second Basement</td><td>899</td><td>1009</td></tr><tr><td>Total</td><td>2035</td><td>2033</td></tr><tr><td>Total ECS</td><td>2035</td><td>677 (3 scooter parking equivalent to 1 car parking)</td></tr><tr><td>Total ECS</td><td colspan="2">2712</td></tr></tbody></table>		Category	FAR (sq m)	Parking Required	No. of ECS Required	Residential Block				Residents	119450.97	1 ECS/75 sq m of FAR	1593	Visitors	---	25% of parking required	398	Total Parking Residential Block			1991	Commercial Block				Residents	28681.27	1 ECS/50 sq m of FAR	574	Visitors		25% of parking required	143	Total Parking Commercial Block			717	Total Parking			2708	Parking	Total Car Parking Provided	Total Scooter Parking provided	Surface	212	0	First Basement	924	1024	Second Basement	899	1009	Total	2035	2033	Total ECS	2035	677 (3 scooter parking equivalent to 1 car parking)	Total ECS	2712	
Category	FAR (sq m)	Parking Required	No. of ECS Required																																																													
Residential Block																																																																
Residents	119450.97	1 ECS/75 sq m of FAR	1593																																																													
Visitors	---	25% of parking required	398																																																													
Total Parking Residential Block			1991																																																													
Commercial Block																																																																
Residents	28681.27	1 ECS/50 sq m of FAR	574																																																													
Visitors		25% of parking required	143																																																													
Total Parking Commercial Block			717																																																													
Total Parking			2708																																																													
Parking	Total Car Parking Provided	Total Scooter Parking provided																																																														
Surface	212	0																																																														
First Basement	924	1024																																																														
Second Basement	899	1009																																																														
Total	2035	2033																																																														
Total ECS	2035	677 (3 scooter parking equivalent to 1 car parking)																																																														
Total ECS	2712																																																															
4.	Project Cost:	INR 590.31 Cr.																																																														
5.	Water Requirement per day & Source	During construction phase and post construction. During construction phase water supply will be taken from private water tankers. During operation phase, source of water will be Municipal Supply or ground water. Permission will be taken from concerned authority for obtaining water during operation phase. Total water requirement for the proposed project is approx. 889 KLD, out of which domestic water requirement is 511.0 KLD. Fresh water requirement for the project is approx. 469 KLD. Quantity of recycled water Treated water from STP will be re-used within project site for flushing, HVAC cooling and landscaping purpose. STP of capacity 330 KLD and 175 KLD will be provided for residential and commercial area respectively. 420 KLD of water will be recycled within project site thereby reducing fresh water demand for the project. 18 KLD of water will be discharged into sewer only during monsoon season.																																																														
6.	Fuel & Energy:-	Maximum power demand for the total project is estimated to be 8969 KVA. Power requirement for residential block is 5292 kVA. Power requirement for commercial block is 3677 kVA. Source of power will be Jaipur Vidyut Vitran Nigam Ltd. through 33 KV sub-station. Details of DG sets are as follows: - Commercial Block: 2 Nos. X 2000 kVA & 1 No. 1500 kVA - Residential Block: 3 Nos. X 1500 kVA, 3 Nos. X 1010 kVA & 1 Nos 500 kVA																																																														

7.	Environment Management Plan with budgetary provision.	Rs. 16.4 Lacs as capital cost and Rs. 9.9 Lacs as annual recurring cost in construction phase and Rs. 130.6 Lacs as capital cost and Rs. 25.2 Lacs as annual recurring cost in operational phase
8.	CSR Activities	Total-Rs. 11.80 Cr. (2% of total project cost (590.31 Cr) will be proposed to spent for CSR Activity The activity will be performed on need base assessment of that area.
9.	STP	STP of capacity 330 KLD & 175 KLD to be provided in residential and commercial block respectively. Technology: MBBR
10.	Green Belt/ Plantation area and % of total area in sq. mts.	Total green area measures 25167.59 m ² i.e. 35.14 % of the net plot area.
11.	Budgetary Breakup for Labour	Rs.50 Lacs

3. The SEAC Rajasthan after due considerations of the relevant documents submitted by the project proponent and additional clarifications/documents furnished to it have recommended for Environmental Clearance with certain stipulations. The SEIAA Rajasthan after considering the proposal and recommendations of the SEAC Rajasthan hereby accord Environmental Clearance to the project as per the provisions of Environmental Impact Assessment Notification 2006 and its subsequent amendments, subject to strict compliance of the terms and conditions as follows:

PART A: SPECIFIC CONDITIONS

I. CONSTRUCTION PHASE

1. Consent to Establish" shall be obtained from RPCB before start of any construction work at the site.
2. The PP shall obtain a "No objection certificate for height clearance for the envisaged level from the Airports Authority of India.
3. No Mobile tower shall be installed.
- ✓ 4. As envisaged, the P.P. shall invest at least an amount of **Rs. 16.4 Lacs** as capital cost and **Rs. 9.9 Lacs** as annual recurring cost in construction phase and **Rs. 130.6 Lacs** as capital cost and **Rs. 25.2 Lacs** as annual recurring cost in operational phase for implementing various environmental protection measures.
- ✓ 5. The PP has proposed an amount of **Rs. 11.80 Crores** under CSR. The expenditure on these activities shall be reflected in the books of account when presented for auditing of accounts. The proposal should contain provision for toilets for girls in nearby schools. The proposal should contain provision for monthly medical camps, distribution of medicines and improvement in educational facilities in the nearby schools. The Detailed action plan of CSR activities shall be submitted by the PP to RSPCB at the time of applying for "Consent to Establish".
6. Green belt/Landscaping should be developed in 25167.59 m² i.e. 35.14 % as proposed.
7. That the grant of this E.C. is issued from the environmental angle only, and does not absolve the project proponent from the other statutory obligations prescribed under any other law or any other instrument in force. The sole and complete responsibility, to comply with the conditions laid down in all other laws for the time-being in force, rests with the industry / unit / project proponent. Any appeal against this environmental clearance shall lie with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under section 16 of the National Green Tribunal Act, 2010.

Wd

8. For conservation of electricity and to reduce energy losses the management shall ensure that the electrical voltage is stepped down from 33 KV to 11 KV and distributed at this level and finally brought to 440 volts.
9. The PP shall obtain approval of drawings of laying electrical lines from the concerned SE of RRVNL/ JVVNL and comply with the provisions as per Terms and Conditions for Supply of Electricity-2004 of JVVNL.
10. The PP shall full fill the requirements of energy regulatory commission.
11. All energy saving measures proposed by the PP should be implemented before the project is put into use.
12. A preventive action plan (as part of conceptual plan) for earthquake resistance buildings as per NBC code specifically for zone 3,4, 5 should submitted along with the form 1 , form 1A and conceptual plan to RSPCB at the time of applying for CTE.
13. Road width and bend should be adequate for easy movement of fire fighting vehicles.
- ✓ 14. The P.P. shall ensure taking necessary steps on urgent basis to improve the living conditions of the labour at site. The proposed Budgetary provision of **Rs. 50 Lacs** shall be made for the housing of construction labor within the site with all necessary infrastructure and facilities such as health facility, sanitation facility, fuel/LPG for cooking, along with safe drinking water, medical camps, and toilets for women, crèche for infants. The housing may be in the form of temporary structures to be removed after the completion of the project. Details of provisions should be submitted to RPCB at the time of obtaining CTE.
15. The drains should be of adequate capacity and be lined till the final disposal points.
16. As proposed, the entire waste water during the construction phase should be discharged through the Septic tank followed by soak pit and during post construction phases through 2 STPs of capacity 330 KLD & 175 KLD to be provided in residential and commercial block respectively based on MBBR Technology. The construction of the STP should be carried out simultaneously with that of the project and the STP should be functional before the project is put into use.
17. All required sanitary and hygienic measures shall be in place before starting construction activities. The safe disposal of waste water and solid waste generated during the Construction phase shall be ensured.
18. All the laborers engaged for construction shall be screened for health and adequately treated before engaging them to work at the site.
19. All the topsoil excavated during the construction shall be stored for use in horticulture/landscape development within the project site.
20. Disposal of muck during construction phase should not create any adverse effect on the neighboring communities and be disposed taking necessary precautions for general safety and health aspects of the people, only at approved sites with the approval of competent authority.
21. Soil and ground water samples will be tested to ascertain that there is no threat to the ground water quality by leaching of heavy metals and other toxic contaminants.
22. Construction spoils, including bituminous material and other hazardous materials must not be allowed to contaminate water courses and the dump sites for such material must be secured so that they do not leach into the ground water.
23. The diesel generator sets to be used during and post construction phase shall be of low-sulphur-diesel type and shall conform to Environment (Protection) Rules for air and noise emission standards.
24. Vehicles hired for bringing construction material and laborers to the site shall be in good conditions and shall conform to applicable air and noise emission standards and shall be operated during non-peak/approved hours.

lul

25. Ambient noise levels shall conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality shall be closely monitored during construction phase.
26. Fly ash shall be used as building material in the construction as per the provisions of Fly Ash notification of September, 1999 and amended as on August, 2003.
27. Ready mixed concrete shall be used in building construction.
28. NOC shall be obtained from National State Disaster Management Authority, wherever applicable.
29. Provision for storm water harvesting and its re-use as per CGWA and BIS standards for various applications should be implemented before the project is put into use.
30. Guidelines issued by concerned Ministry for water scarce areas may be followed.
31. Water demand during construction shall be reduced by the use of pre-mixed concrete, curing agents and other best practices. In place of fresh water, effort should be made to use treated waste water from nearby areas.
32. Total domestic water requirement shall not exceed **889 KLD**, as proposed. The necessary permission of water supply should be submitted to RSPCB at the time of applying for CTE. At the time of applying for CTE the PP should get it confirmed from RSPCB that no illegal bore well exists in the proposed site.
33. Building Plan should be got approved from the competent Authority and the construction should be as per the approved building plan and as per applicable provisions in NBC.
34. The P.P. should ensure compliance of the order of the Hon'ble Rajasthan High Court, Jodhpur, in D. B. Civil writ petition no. 1536 of 2003 in the matter of Abdul Rahman vs. State of Rajasthan and others.
35. Adequate measures shall be taken to reduce air and noise pollution during construction as per CPCB norms.
36. Fixtures for showers, toilet flushing and drinking shall be of low flow either by use of aerators or pressure reducing devices or sensor based control.
37. Use of glass may be reduced by up to 40% to reduce the electricity consumption and load in air-conditioning. If necessary, use high quality double glass with special reflective coating windows.
38. Roofing should meet prescriptive requirement as per Energy Conservation Building Code by using appropriate thermal insulation material to fulfill requirement.
39. Opaque walls shall meet prescriptive requirement as per Energy Conservation Building Code for all air-conditioned spaces, whereas, for non- air-conditioned spaces, by use of appropriate thermal insulation material to fulfill the requirement.
40. Provision of solar water heating /chilling/street lighting etc shall be explored and implemented.
41. Review and revise the requirement of DG set capacities for 100% power back up through optimization of power back up in case of power failure and emergency.
42. A First Aid Room should be provided at the project site, both, during construction and operation phase of the project.
43. Any hazardous waste generated during construction phase shall be disposed of as per applicable rules and norms with necessary authorization of the RPCB.
44. The approval of the competent authority shall be obtained for structural safety of the building due to earthquake, adequacy of firefighting equipment, etc. as per National Building Code 2005 including protection measures from lightening etc.
45. Regular supervision of the above and other measures for monitoring shall be in place throughout the construction phase, so as to avoid nuisance to the surroundings.
46. During construction phase and Post construction / operation phase of the project, the project proponent shall be responsible for implementation of EIA/EMP. Commitment of proponent in this regard shall be submitted to RPCB at the time of applying for CTE.

Wd

47. The project proponent shall fulfill in letter and spirit, all the commitments given/submitted to the SEAC office.

II OPERATION PHASE

1. shall certify the installation of the Sewage Treatment Plant (STP) and a report in this regard shall be submitted to the RPCB, before the project is commissioned for operation. Discharge of treated sewage shall conform to the norms & standards of the Rajasthan State Pollution Control Board.
2. Adequate measures shall be taken to prevent odor from solid waste processing and STP.
3. Proper system of channelizing excess storm water shall be provided.
4. Rain Water harvesting (RWH) for roof top run-off and surface run-off, as planned shall be implemented. Before recharging the surface run off, pre-treatment must be done to remove suspended matter, oil and grease. The Rain Water Harvesting plan shall be as per GoI manual.
5. The proposals on the energy conservation measures confirming to energy conservation norms finalized by Bureau of Energy Efficiency shall be implemented.
6. The power factor shall be maintained near unity.
7. Application of solar energy shall be incorporated for illumination of common areas, lighting for gardens and street lighting in addition to provision for solar water heating. A hybrid system or fully solar system for a portion of the apartments shall be provided.
8. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking shall be fully internalized and no public space shall be utilized.
9. Regular and periodic mock drills shall be undertaken by the fire department at least once in a year.
10. The D. G. sets to be operated with stack height as per EP Act, 1986 along with acoustic enclosure.
11. Incremental pollution loads on the ambient air quality noise and water quality shall be periodically monitored after commissioning of the project and report to be submitted to RPCB.
12. The solid waste generated shall be properly collected & segregated before disposal to the City Municipal Facility. The in-vessel bio-conversion technique may be used for composting the organic waste.
13. Any hazardous waste including biomedical waste shall be disposed of as per applicable Rules & norms with necessary approvals of the Rajasthan State Pollution Control Board.
14. The green belt design along the periphery of the plot shall achieve attenuation factor conforming to the day and night noise standards prescribed for residential land use. The proposed open space inside the plot shall be suitably landscaped and covered with vegetation of indigenous variety.
15. Trees and shrubs of local species shall be planted to allow habitat for birds with appropriate distance from the boundary.
16. The SEIAA, Rajasthan reserve the right to add new conditions, modify/ annual any condition and/or to revoke the clearance if implementation of any of the aforesaid condition/other stipulations imposed by competent authorities is not satisfactory. Six monthly compliance status report of the project along with implementation of environmental measures shall be submitted to MoEF, Regional Office, Lucknow, SEIAA, Rajasthan & RPCB, Jaipur.

B GENERAL CONDITIONS

1. The environmental safeguards contained in Form 1-A shall be implemented in letter and spirit.
 2. Six monthly monitoring reports shall be submitted to SEIAA, Rajasthan and Rajasthan State Pollution Control Board.
 3. Officials of the RPCB, who would be monitoring the implementation of environmental safeguards, shall be given full cooperation facilities and documents/data by the PP during their inspection. A complete set of all the documents submitted to SEIAA, Rajasthan shall be forwarded to the DoE, Rajasthan and Rajasthan State Pollution Control Board.
 4. In case of any change(s) in the scope of the project, the PP requires a fresh appraisal by SEIAA/SEAC, Rajasthan.
 5. The SEIAA/SEAC, Rajasthan reserves the right to add additional safeguard measures subsequently, if found necessary, and to take action including revoking of the environmental clearance under the provisions of the Environment (Protection) Act-1986, to ensure effective implementation of the suggested safeguard measures in a time bound and satisfactory manner.
 6. All the other statutory clearances such as the approvals for storage of diesel from the Chief Controller of Explosives, Fire department, Civil Aviation Department, Forest Conservation Act, 1980 and
- lul*

Wildlife (protection) Act, 1972 etc. shall be obtained, as may be applicable, by PP from the competent authority.

7. The PP shall ensure advertising in at least two local news papers widely circulated in the region, one of which shall be in vernacular language that, the project has been accorded environmental clearance and copies of the clearance letters are available with SEIAA, Rajasthan and the Rajasthan State Pollution Control Board and may also be seen on the website of the Board at www.rpcb.nic.in. The advertisement shall be made within 7(seven) days from the date of issue of the environmental clearance and a copy shall also be forwarded to the SEIAA, Rajasthan and Regional Office, Jaipur(S) of the Board.
8. These stipulations would also be enforced amongst the others under the provisions of Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986, the Public Liability (Insurance) Act, 1991 and EIA Notification' 06.
9. Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the proponent, if it is found that construction of the project had been started without obtaining environmental clearance.


(Rajesh Kumar Grover)
Member Secretary,
SEIAA Rajasthan.

No. F1 (4)/SEIAA/SEAC-Raj/Sectt/Project/Cat. 8(a)B2 (1352)/14-15

Copy to following for information and necessary action:

1. Secretary, Ministry of Environment, Forest & Climate Change, Govt. of India, Indira Paryavaran Bhawan, Jor Bagh Road, Aliganj, New Delhi-110003.
2. Addl. Chief Secretary, Environment Department, Rajasthan, Jaipur.
3. Smt. Alka Kala, Chairperson, SEIAA, Rajasthan, 69-A, Bajaj Nagar Enclave, Jaipur
4. Sh. Sankatha Prasad, (IFS Retd.), 250, Gomes Defence Colony, Vaishali Nagar, Jaipur.
5. Member Secretary, Rajasthan State Pollution Control Board, Jaipur for information & necessary action and to display this sanction on the website of the Rajasthan Pollution Control Board, Jaipur.
6. Secretary, SEAC Rajasthan.
7. The CCF, Regional Office, Ministry of Environment & Forests, RO(CZ), Kendriya Bhawan, 5th Floor, Sector 'H', Aliganj, Lucknow-226 020.
8. Environment Management Plan- Division, Monitoring Cell, MoEF, Paryavaran Bhawan, CGO Complex, Lodhi Road, New Delhi-110003.
9. Programmer, Department of Environment, Government of Rajasthan, Jaipur with the direction to upload the copy of this environmental clearance on the website.

/
M.S. SEIAA (Rajasthan)